BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/BD/WORK_INDENT13159

APPROVED SCHEDULE - B

No EE/BTP/BBMP/E-PMT/07/2014-15, Date: 31.10.2014

Construction of floor to Library Building at HMT layout 1st Block in ward No 09(Change of place and work: Construction of Library Building at HMT Layout 1st Block in Ward No. 09 Phase-1)

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of GOPINATHREDDY	
				In Figures	In Words
1	103.04	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459 cum wuth superplastisier @ 3lts confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not	Cum	5600.0	Rupees Five Thousand Six Hundred Only
2	123.65	Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery TMT Bars Fe 550 etc complete as per specifications and directions of engineer in charge of the work.	Qtl	7500.0	Rupees Seven Thousand Five Hundred Only
3	224.45	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work.	Sqm	280.0	Rupees Two Hundred Eighty Only
4	360.14	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and sofits of beams , beam haunchings, cantilever girders, bresumers and lintels not exceeding 1 m in depth including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work.	Sqm	250.0	Rupees Two Hundred Fifty Only
5	489.63	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work.	Sqm	330.0	Rupees Three Hundred Thirty Only
6	1.8	Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc., including edges including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work.	Sqm	270.0	Rupees Two Hundred Seventy Only
7	422.28	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	200.0	Rupees Two Hundred Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

8	400.49	Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	223.0	Rupees Two Hundred Twenty Three Only
9	822.77	Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	22.0	Rupees Twenty Two Only
10	339.57	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	190.0	Rupees One Hundred Ninety Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92